

# SECTION-1 TABLE — A: TIME AND WORK FRAME

FOR THE WORK UNDER- STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA

MANUAL BIDS SHALL NOT BE ACCEPTED.

### CRITICAL DATE SHEET

CHITICAL DE	11-011-
Bid Start Date	22/02/2024
Bid Document Download / Sale Start Date	22/02/2024
Bid Submission Closing Date	13/03/2024at 15:00
Technical Bid Opening Date	14/03/2024at 15:30
Financial Bid Opening Date/Time	After Opening Technical Bid
Validity of Bid	120 days from the date of opening.
	Bid Start Date  Bid Document Download / Sale Start Date  Bid Submission Closing Date  Technical Bid Opening Date  Financial Bid Opening Date/Time



- The Archaeological Survey of India Agra Circle, Agra invites Online Bids in the prescribed form under the double Bid system i.e. technical and Financial Bid for supply of materials work STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA
- 1. The system of e-tendering shall be adopted as double Bid. Tender documents may be downloaded from CPPP site <a href="https://eprocure.gov.in/eprocure/app">https://eprocure.gov.in/eprocure/app</a> as per the schedule as given in CRITICAL DATE SHEET.

#### 2. Bid Submission:

Applicants/ intending or interested Bidders are invited to submit their online proposal after carefully reading the Request for Proposal (RFP) by providing necessary document and submission of BOQ. Such proposal are to be submitted online within the stipulated date and time as mentioned in the Tender Document and as given in CRITICAL DATE SHEET. Bids shall be submitted online only at CPPP website: https://eprocure.gov.in/eprocure/app.

Bid documents may be scanned with 100 dpi with black and white option which help in reducing size of the scanned document.

#### 3. Earnest Money Deposit:

The Hard Copy of original instruments in respect of cost of earnest money must be deposited to the SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA, AGRA CIRCLE, 22 MALL ROAD, AGRA on or before Tender opening date/ time as mentioned in critical date sheet.

The offer without EMD will be rejected summarily. EMD is to be supplied by all the bidders except those who are registered with Central Purchase Organization, National Small Industries Corporation (NSIC)/ MSME.

## 4. <u>Tender cost Of Tender:</u> RS. 12,78,620/- (Rs. TWELVE LAKHS SEVENTY EIGHT THOUSAND SIX HUNDRED TWENTY ONLY)

-: Contact Details:-

Contact Person	SUPERINTENDING ARCHAEOLOGIST
Address for communication	SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA, AGRA CIRCLE, 22 MALL ROAD,AGRA e-mail – circleagra.asi@gov.in
Contact No.	0562- 2227261





#### प्रत्नकीर्सिमपावृणु FILE NO-03/ITD/38/2023-2024/W GOVERNMENT OF INDIA

भारत सरकार

Office of the Superintending Archaeologist कार्यालय अधीक्षण पुरातत्विद् Archaeological Survey of India भारतीय पुरातत्व सर्वेक्षण Agra Circle, 22 Mall Road, Agra 282001 आगरा मण्डल, 22 माल रोड, आगरा 282001

NOTICE INVITING TENDER निविदा आमंत्रण स्चना

The Superintending Archaeologist, Archaeological Survey of India, Agra Circle, Agra, invites e-tender on the behalf of the President of India, through CPP Portal for the following works as per specification given below under the work STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA from the registered contractors of Archaeological Survey of India/State PWD or any Central Government Department.

अधीक्षण पुरातत्विवद्, भारतीय पुरातत्व सर्वेक्षण आगरा मण्डल, आगरा भारत के राष्ट्रपति की ओर से सी० पी० पी० पोर्टल के माध्यम से कार्य STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA हेतु भारतीय पुरातत्व सर्वेक्षण / राज्य पी०डब्ल्यू०डी० या केंद्र सरकार के किसी विभाग के पंजीकृत ठेकेदारों से ई टेंडर आमंत्रित करता है।

#### Eligibility Criteria: -

पात्रता मापदंड:-

- 1. The firm/Agency should have registration in ASI / any Central Government Department or State PWD for civil works.
- क. फर्म / एजेंसी का सिविल कार्यों के लिये भारतीय पुरातत्व सर्वेक्षण / केंद्र सरकार या स्टेट पीoडबल्यूoडीo में पंजीकरण होना चाहिये।
- 2. The firm/Agency should have GST registration.
- ख. फर्म / एजेंसी के पास जी० एस० टी० पंजीकरण होना चाहिये।
- 3. The firm/Agency should have Pan Card.
- ग. फर्म / एजेंसी के पास पेन कार्ड होना चाहिये।
- 4. The Firm/Agency should have income tax return for three financial year 2019-2020, 2020-2021 and 2021-2022. (A.Y. 2020-2021, 2021-2022, & 2022-2023).
- घ. फर्म / एजेंसी को तीन वित्तीय वर्ष 2019—2020, 2020—2021 एवं 2021—2022 (निर्धारण वर्ष 2020—2021, 2021—2022 एवं 2022—2023) का आयकर रिटर्न भरा होना चाहिये।
- 5. The firm/agency should have average annual financial turnover for financial year 2019-2020, 2020-2021 and 2021-2022, should be at least 30% of the tender cost i.e. Rs. 3,83,586/-. A certificate in this regard issued by the CA has to be submitted.
- च. फर्म /एजेंसी के पास 3 वर्षों 2018—2019, 2019—2020 एवं 2020—2021 के दौरान औसत वार्षिक वित्तीय करोबार निविदा राशि का कम से कम 30 प्रतिशत होना चाहिये यानी रु0 3,83,586/- जिसे सी0 ए0 द्वारा जारी प्रमाण पत्र के रुप में प्रस्तुत करना होगा।
- 6. The firm / agency should have experience for completion of similar nature of work (Means the bidder should have the experience for supply of materials for conservation work or the complete work for the conservation of heritage monuments) at Monuments/heritage sites at least three works each costing not less than 40% of the tender cost i.e. 5,11,448/- OR Two works each Costing not less than 50% of the tender cost i.e. Rs. 6,39,310/- OR One similar work costing not less than 80% of the tender cost i.e. Rs. 10,22,896/-. And that/those work/works should have been completed in the last 7 years ending last day of the month, previous to the month of floating of the tender.

फर्म/एजेंसी के पास कम से कम तीन स्मारकों/विरासत स्थलों पर समान प्रकृति के काम को पूरा करने का अनुभव होना चाहिए (मतलब बोली लगाने वाले के पास संरक्षण कार्य के लिए सामग्री की आपूर्ति या विरासत स्मारकों के संरक्षण के लिए पूरा काम करने का अनुभव होना चाहिए) तीन कार्य प्रत्येक की लागत निविदा लागत का 40% यानी 5,11,448/- से कम नहीं होनी चाहिए या दो कार्य प्रत्येक की लागत निविदा लागत का 50% यानी रु. से कम नहीं होनी चाहिए। 6,39,310/- या एक कार्य की लागत निविदा लागत का 80% यानी रु. से कम नहीं होनी चाहिए। 10,22,896/-. और वह/वे कार्य/कार्य पिछले 7 वर्षों में, निविदा जारी होने के माह से पहले, माह के अंतिम दिन तक पूरे हो जाने चाहिए।

STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA

7. Copy of work order and completion certificate should be uploaded on CPP Portal as per tender

ज. कार्य आदेश और पूर्णता प्रमाण पत्र की प्रतिलिपि आवश्यक निविदा के अनुसार सी० पी० पी० पोर्टल पर अपलोड़ की जानी चाहिये।

The eligible Contractors may upload their tender documents online only at CPPP website: https://procure. gov.in/ eprocure /app. upto 15:00 hours of 13/03/2024which will be opened on dated 14/03/2024at 15:30 hours.

पात्र ठेकेदार केवल सी० पी० पी० वेबसाईट http://eprocure.gov.in/eprocure/app पर अपने निविदा दस्तावेज दिनांक 13/03/2024at 15:00 तक ऑनालाइन अपलोड कर सकते हैं जो दिनांक 14/03/2024at 15:30 खोला जाएगा।

TENDER COST RS. 12,78,620/- (Rs. TWELVE LAKHS SEVENTY EIGHT THOUSAND SIX HUNDRED TWENTY ONLY)

अनुमानित राशि:- रु० 12,78,620/- (रु० बारह लाख अठत्तर हजार छः सौ बीस मात्र)

EARNEST MONEY RS. 31,966/- (THIRTY ONE THOUSAND NINE HUNDRED SIXTY SIX ONLY) बयाना राशि:- रु० 31,966/- (रु० एकतीस हजार नौ सौ छियासठ मात्र)

(Exemption as per rules)

(नियमानुसार छूट)

The earnest money should be in the form of FDR drawn in favour of the "SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA" Payable at Agra of any scheduled bank guaranteed by the Reserve Bank of India and enclose with the tender.

अमानत राशि एफ0 डी0 आर0 के रुप में निविदा के साथ संलग्न होना चाहिए जो "भारतीय रिजर्व बैंक द्वारा समर्थित आगरा के किसी भी अनुसूचित बैंक में अधीक्षण पुरातत्विवद्, भारतीय पुरातत्व सर्वेक्षण, आगरा मण्डल, आगरा के पक्ष में देय हो।

Time allowed for completion of work will be 150 days which will be reckoned with in fifteen days from the date of issue of order. Tenders of the contractors who do not deposit earnest money in favour of the SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA, AGRA CIRCLE in the prescribed form will be liable to be summarily rejected.

कार्य पूरा होने के लिए अनुमत समय 150 दिन होंगा जिसे कार्य आदेश जारी होने की तारीख से पंद्रह दिनों के अंदर से माना जाएगा। उन ठेकेदारों की निविदाएं निरस्त मानी जाएगी जो अधीक्षण पुरातत्विवद्, भारतीय पुरातत्व सर्वेक्षण, आगरा मण्डल, आगरा के पक्ष

में निर्धारित राशि जमा नहीं करते हैं।

Conditions and tender forms can be downloaded from our ASI website www.asiagracircle.in and eportal eprocure.gov.in. w.e.f. 22/02/2024 to 13/03/2024upto 15:00 hours of each day.

निविदा शर्ते एवं प्रपत्र हमारी वेबसाईट <u>www.asiagracircle.in</u> और e-portal <u>eprocure.gov.in</u>. से दिनांक 22/02/2024 से दिनांक 13/03/2024upto 15:00 बजे तक डाउनलोड किए जा सकते हैं।

No tender shall be entertained after this deadline under any circumstances what so ever. The Bids of tenders will be opened on 14/03/2024AT 15:30 HRS. in the presence of authorized representative of Bidders as may wish to be personally present.

इस समय सीमा के बाद किसी भी परिस्थिति में कोई भी निविदा पर विचार नहीं किया जाएगा। निविदाओं की तकनीकि बोलियां बोलीदाताओं के अधिकृत प्रतिनिधि की उपस्थिति में या व्यक्तिगत रुप से उपस्थिति में दिनांक 14/03/2024 को 15:30 बजे खोली

Tender documents are available in the ASI website www.asiagracircle.in and e-portal eprocure.gov.in. The bidder must attach the copy of EMD should be deposited in ASI, Agra Circle Agra on or before the date of opening the tender.

भारतीय पुरातत्व सर्वेक्षण, आगरा की वेबसाईट <u>www.asiagracircle.in</u> और e-portal <u>eprocure.gov.in</u>. पर निविदा दस्तावेज उपलब्ध हैं। बोली लगाने वाले को तकनीकि निविदा खोलने से पहले भारतीय पुरातत्व सर्वेक्षण, आगरा मण्डल, आगरा में बयाना राशि की प्रति जमा करनी होगी।

The Archaeological Survey of India reserves the right to amend or withdraw any of the terms and conditions contained in the Tender Document or to reject any or all tenders without given any notice or assigning any reason. The decision of the Archaeological Survey of India, in this regard shall be final and binding on all parties in all circumstances.

भारतीय पुरातत्व सर्वेक्षण निविदा दस्तावेज में शामिल किसी भी नियम और शर्तों को संशोधित करने या वापस लेने या किसी भी नोटिस दिए बिना या कोई कारण बताए किसी भी या सभी निविदाओं को अस्वीकार करने का अधिकार सुरक्षित रखता है। इस सम्बंध में

भारतीय पुरातत्व सर्वेक्षण का निर्णय सभी परिस्थितियों में सभी पक्षों पर अंतिम और बाध्यकारी होगा।

NAME OF WORK: STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA

REPARTOR

Earth work in excavation by manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including estressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Rate Including GST).  Tile brick masonry with common burnt, day F.P.S. (non modular) tile bricks of class designation 10 in foundation and plinth in. Cement motorar 1.6 (1 cement : 6 coarse sand) (Rate Including GST).  Taking out lakhauri brick work manually for fixing of Y Shape Post of concertina coll fencing including stacking of sérviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level 1.2.4 (1 cement 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources; (Rate Including GST).  Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and dilling holes up to 10 mm dia! etc. complete with welding & cutting (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1.3.6 (1 cement 3 coarse sand (zone-III) derived from natural sources; (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 11.3.6 (1 cement 3 coarse sand (zone-III) derived from natural sources; 6 graded stone aggregate 20 mm nominal size derived from natural sources; 16 graded stone aggregate 3 coarse sand (zone-III) derived from sture in second pattern with angle iron frames (6xx6xx6) mm size graded with 50xx6	NAME OF WORK: STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZ	The state of the s	
Earth work in excavation by manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sgm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Rate Including GST).  Tile brick masonry with common burnt, clay F.P.S. (non modular) tile bricks of class designation 10 in foundation and plinth in Cement mortar 1.6 (1 cement : 6 coarse sand) (Rate Including GST).  Taking out lakharuh brick work manually for fixing of Y Shape Post of concertina coil fencing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1.2.4 (1 cement .2 coarse sand (zone-III) derived from natural sources). (Rate Including GST).  Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm dial etc. complete with welding & cutting (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1.3.6 (1 cement .3 coarse sand (zone-III) derived from natural sources). (Rate Including GST).  Providing Another of the service of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1.3.6 (1 cement .3 coarse sand (zone-III) derived from natural sources (8 graded stone aggregate .20 mm nominal size derived from natural sources) (Rate Including GST).  Providing A fixing of M. S. Iron Gates Such as Iron frames (5bx50x6)mm size. (Experiment of the service		Qt	у.
class designation 10 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) (Rate Including GST).  Taking out lakhauri brick work manually for fixing of Y Shape Post of concertina coil fencing including stacking of serviceable material and disposal of unserviceable material within 50 metres liead as per direction of Engineer-in-charge (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2-4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) (Rate Including GST).  Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be spit and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm dial etc complete with welding & cutting. (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources) (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:8 (1 cement : 3 coarse sand (zone-III) derived from natural sources) (Rate Including GST).  Providing Charges for MS. Iron Gates Such as iron frames (60x50x6)mm size. 2 center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing & fixing of M.S. Jaal on Well of required pattern with angle iron frames (60x65x6) mm size graded with 50x50x6 imm angle cc 50 cm, having flat 40x6 mm cc 10 cm and covered with fron mesh Jalie and nut bolts including and laying approved brand and pattern over and including GST).  Providing and l	Earth work in excavation by manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Rate	14.76	Cum
coil fencing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources: (Rate Including GST).  Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm fdal etc. complete with welding & cutting. (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:3:6 (1 cement: 3 coarse sand (zone-III)) derived from natural sources: 6 graded stone aggregate 20 mm nominal size derived from natural sources; (Rate Including GST).  Repairing Charges for M.S. Iron Gates Such as iron frames (50x50x6)mm size 2 (20 mm nominal size derived from natural sources); (Rate Including GST).  Providing and locking arrangement as per required and nut botts including cutting fabricating welding etc. complete. (Rate Including GST).  Providing and laying 60 mm Well of required pattern with angle iron frames (65x65x6) mm size graded with 50x50x6 mm angle: c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut botts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and applying a priming coat of readymade Dustbins of Red Sand Stone of Cylindrical shape in	class designation 10 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6	14.30	Cum
Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement 2 coarse sand (2one-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) (Rate Including GST).  Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm dial etc. complete with welding & cutting (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level   1:3:6 (1 cement 3 coarse sand (2one-III) derived from natural sources) (Rate Including GST).  Repairing Charges for M.S. Iron Gates Such as iron frames (50x50x6)mm size, 12mm Square Bar, M.S. Flat 50x5 mm, Gusset plate 6mm thick at corners & center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).  Providing & fixing of M.S. Jaal on Well of required pattern with angle iron frames (60x56x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).  Supply & Fixing Red sand stone benches having 2 legs of size 0.50x0.20x0.45 m as per design and matching to the existing pattern at site. (Rate Incl	Taking out lakhauri brick work manually for fixing of Y Shape Post of concertina coil fencing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-	2.71	Cum
including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm dial etc. complete with welding & cutting. (Rate Including GST).  Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 11:3.6 (1 cement 3 coarse sand (zone-III) derived from natural sources) (Rate Including GST).  Repairing Charges for M.S. Iron Gates Such as iron frames (50x50x6)mm size. 12mm Square Bar, M.S. Flat 50x5 mm, Gusset plate 6mm thick at corners & center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).  Providing & fixing of M.S. Jaal on Well of required pattern with angle iron frames (65x65x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick racing acted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).  1. Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design, (Rate Including GST).  Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved brand and manufacture of required colour to give an even shade two or more coats on new work over an under c	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate	2.71	Cum
cost of centering and shuttering - All work up to plinth level 13:36 (1 cement 3 coarse sand (2one-III) derived from natural sources: 6 graded stone aggregate 20 mm nominal size derived from natural sources) (Rate Including GST).  Repairing Charges for M.S. Iron Gates Such as iron frames (50x50x6)mm size, 12mm Square Bar, M.S. Flat 50x5 mm, Gusset plate 6mm thick at corners & center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).  Providing & fixing of M.S. Jaal on Well of required pattern with angle iron frames (65x65x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).  Supply & Fixing Red sand stone benches having 2 legs of size 0.50x0.20x0.45 m with simple moldings and 80 mm thick red sand stone-top size 1.50x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).  Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).  Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved brand and manufacture of required colour to give an even shade: two or more co	Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm dia etc. complete with welding & cutting.	603.00	Kg
12mm Square Bar, M.S. Flat 50x5 mm, Gusset plate 6mm thick at corners & center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).  Providing & fixing of M.S. Jaal on Well of required pattern with angle iron frames (65x65x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).  Supply & Fixing Red sand stone benches having 2 legs of size 0.50x0.20x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).  Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).  Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Real Including GST).  Structural steel etc. complete. (Rate Including GST).  STRUCTURAL REPAIR WORK ATCHINEKA-RAUZA, AGRA	cost of centering and shuttering - All work up to plinth level 1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) (Rate Including GST).	3.33	Cum
(65x65x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).  Discipling & Fixing Red sand stone benches having 2 legs of size 0.50x0.20x0.45 m with simple moldings and 80 mm thick red sand stone-top size 1.50x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).  Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).  Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture (Rate Including GST).  STRUCTURAL REPAIR WORK AT CHINI: KA-RAUZA, AGRA	12mm Square Bar, M.S. Flat 50x5 mm, Gusset plate 6mm thick at corners & center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).	1.00	Job
Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).  Supply & Fixing Red sand stone benches having 2 legs of size 0.50x0.20x0.45 m with simple moldings and 80 mm thick red sand stone top size 1.50x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).  Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).  Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture (Rate Including GST).  STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA	(65x65x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using	384.83	Kg
m with simple moldings and 80 mm thick red sand stone-top size 1.50x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).  1 Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).  2 Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  3 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. (Rate Including GST).  STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).	47.25	Sqm
Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).  Providing & fixing of M.S. XPN Jali over M.S. Iron Gate including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. (Rate Including GST).  STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA  STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA	m with simple moldings and 80 mm thick red sand stone top size 1.50x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).	10.00	Nos
fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).  Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. (Rate Including GST).  STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA	Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design (Rate Including GST).	3.00	Nos
required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. (Rate Including GST).  STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA	fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete. (Rate Including GST).	76.81	Kg
STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA	required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture (Rate Including GST).	116.80	Sqm
Porter de la	s per included the later of the second of th	(\$) (\$)	agreement the state of
	parer all all cast	180	gra Circle

14	Providing & fixing of G.I. Barbed wire Fencing with existing Red Sand Stone Pillar placed barbed wire weighting 9.38 kg per100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Rate	840.00	Rmt
15	Including GST).  Surface dressing of the ground including removing vegetation and inequalities		
	not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil (Rate Including GST).	150.00	Sqm
16	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with Jamuna sand, with common burnt clay non modular bricks. (Rate Including GST).	150.00	Sqm
	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately). (Rate Including GST).	158.00	Sqm
18.	Providing & fixing M.S. gates of required pattern with angle iron frames (50x50x6)mm size graded with 10 cm c/c Sq. bars 12mm size pointed at the top extra with same curved bar and each frame having Gusset plate 6mm thick at corners & center and provision for hinges and locking arrangement with M.S. iron gurders of required size and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).	583.20	Kg
19.	Supply of 1st quality Unslaked lime in sealed air tight bags. (Gotan) (Rate Including GST).	110.69	Qtl.
20.	Supply of Surkhi of 1st class well burnt bricks. (Rate Including GST).	17.60	Cum.
21.	Supply of Sieved Coarse Sand (Screened) free from lumps, dust, silt & organic impurities - Kalpi/Dholpur Quarry. (Rate Including GST).	17.60	Cum.
22.	Supply of Lakhauri Bricks Nominal Size: (Rate Including GST).	30.52	Cum.
23.	Supply of Brick Ballast of Lakhori Brick/ 1st class srick 25 mm size (Rate Including GST).	25.02	Cum.
24.	Supply of White lime of Ist Quality. (Rate Including GST).	33.58	Kg.
	Supply of Marble Chips. (Rate Including GST).	67.15	Kg.
	Supply of Red Sand Stone size 65 mm thick (Bansi Paharpur/Tantpur). (Rate Including GST).	10.20	Sqm
27.	Supply of Red sand stone thick of different size as per site requirement. (Bansi Paharpur/Tantpur). (Rate Including GST).	3.87	Cum.
28.	Supply of Brick Jeera of 1st class brick (Rate Including GST).	8.25	Cum.

#### **Evaluation Criteria**

1- All documents to be uploaded in CPPP portal properly.

2- This is not an item wise bid. The L1 will be selected depending upon the overall lowest bid of all the items.

3- The bidders are requested to visit the site and examine the requirement and its rate accordingly before quoting the rate in Online BOQ. If the Quoted rate is obvious Vague (Extremely High or Extremely Low) the same will not be considered and may be rejected at Financial Stage.

Superintending Archaeologist

STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA

TERMS AND CONDITION FOR SUBMISSION OF TENDER

- 1. Tenders are hereby invited on behalf of the President of India. For the work under Tender cost of RS. 12,78,620/- (Rs. TWELVE LAKHS SEVENTY EIGHT THOUSAND SIX HUNDRED TWENTY ONLY)
- Tender document consisting of the detailed plans, complete specifications, the schedule of quantities of the various items of work to be done, and the set of conditions of contract to be complied with by the person whose tenders may be accepted. The tender forms can be downloaded from our website- www.asiagracircle.in and e-portal eprocure.gov.in from 22/02/2024 to 13/03/2024.
- 2 (a) The site of the work is available, or the site for the work shall be made available by the department.
- The Contractors should upload their tender documents online only at CPPP website: https://eprocure.gov.in/eprocure/app. up to 15:00 hours of 13/03/2024which will be opened on dated 14/03/2024at 15:30 hours.
- The time allowed for the work will be 150 days which will be reckoned after fifteen days from the date of issue of order to commence work.
- 3. The contractors should quote in figures as well as in words the rate and amount tendered by them. The amount for each item should be worked out and the requisite totals given.
- 4. When the contractors signs a tender in an Indian Language the percentage above or below and the tendered amount in case of CPWD form No.7 and the total amount tender in the case of CPWD form No.7 and total amount tendered in the case of CPWD form No.8 and should also be written in the same language. In a case of illiterate contractors the rates or the amounts tendered should by attested by a witness.
- 5. Issue of tender form will be stopped one days before the date fixed for opening of tender.
- 6. Earnest money amounting of RS. 31,966/- (THIRTY ONE THOUSAND NINE HUNDRED SIXTY SIX ONLY)
- (unless exempted) in deposit at call received/FDR of scheduled bank guaranteed by the Reserve Bank of India must accompany each tender. 7. The contractor whose tender is accepted (unless exempted ) will be required to furnish by way of security deposit for the due fulfillment of his contract.
- In the case of works costing up to Rs. 1,00,000/- to 10% of the tender cost of work put to tender.
- II) In the case of works costing more than Rs.1,00,000/- and up to 2,00,000/- to 10% on the first Rs.1,00,000/- and 7 % on the balance.
- III) In the case of works costing more than Rs.2,00,000/-, 10% on the first Rs.1,00,000/-, 7 % on the next Rs. 1,00,000/- and 5% on the
- 8. The security amount will be deposited by contractor in the form of FDR/CDR of any Bank RBI pledged to the Superintending Archaeologist, Archaeological Survey of India, Agra Circle, Agra. Earnest money deposited at the time of tender, will be treated as a part of the security deposit. The security amount will also be accepted in the shape of Government securities. Fixed deposit receipt of schedule banks will be accepted for this purpose provided confirmatory advise is forthcoming from the Reserve Bank of India. Validity of FDR must be minimum of 12 Months must be issued form centralized bank.
- 9. The right of acceptance of a tender will be with SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA, AGRA CIRCLE, AGRA who does not bind himself to accept the lowest tender and reserves to himself the authority to reject any or all of the tenders received without assignment of a reason. All tenders in which any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.
- 10. Canvassing in connection with tenders is strictly prohibited and the tenders submitted by the contractors who resort to Canvassing will be liable to rejection.
- 11. All rates shall be quoted on the proper form of the tender alone.
- 12. The criteria for approval of the lowest tender is over all lowest one against the total cost of the tender amount of all tenders.
- 13. On acceptance of the tender, the name of the accredited representative(s) of the contractor who would be responsible for taking instructions from the Engineer in charge shall be communicated to the Engineer in charge.
- 14-Special care should be taken to write the rates in figures as well as in words and the amounts in figures only, in such a way that interposition is not possible. The total amount should be written both in figures and words. The case of figures, the word Rs. should be written before rupees and word (P) after the decimal figures e.g. 2.15 p and case of words the word (Rupees) should proceed and the word 'only' it should in variably up to decimal places. While quoting the area in the schedule of quantities the word only should be written closely following the amount and it should not be written closely following the amount and it should not be written in the next line
- 15. The President of India does not bind himself to accept the lowest or any tender and reserves to himself the right of accepting the whole or any part of the tender and tenderer shall be bound to perform the same at the rates quoted.
- 16. GST or any other or material in respect of this contracts shall be payable by the contractor and Government will not entertain any claim whatsoever in this respect.
- 17. The Contractor shall not be permitted to tender for works in the ASI circle (responsible for award and supply of the contracts) in which his near relative is posted as an officer in any capacity between the grades of Superintending Engineer and Assistant (both inclusive). He shall also intimate the names of persons who are working with him in capacity or are subsequently employed by him and who are near relatives to any Gazetted officer in ASI or in the Ministry of Tourism and Culture by the contractor should render him liable to be removed from the approved list of contractors of this Department.
- 18. The tender of works shall remain valid for a period of 120 days from the date of opening of tenders. If any tender withdraws his tender before the said period or make any modifications in the terms and conditions of the tender, which are not acceptable to the department. Then the Government shall forfeit 100% of the said earnest money absolutely.
- 19. Contractors exempted from payment of Earnest money and Security Deposit in individual cases should attach with the tender an attested Copy of Competent authorities letter exempting them from the payment of Earnest Money and Security Deposit and should produce the original whenever called upon to do so.
- 20. The tender for the work shall not be witnessed by a contractor or contractors who himself/themselves has /have tendered or who may and has /have rendered for the same work. Failure to observe this condition would render of the contractors tendering as well as witnessing the tender liable to summary rejection.
- 21. The copy of uploaded document should be submitted to this office along with the EMD and tenders fee before opening of tender. Should this tender be accepted, I/we hereby agree abide by and fulfil all the terms and provisions of the said conditions annexed hereto so

far as applicable and or in detail thereof to forfeit and pay to the President of India or his successor in office the sum of money mentioned in the said conditions. F.D.R. vide forwarded herewith is (Rupees sum as earnest money and a sum of Rs. (Rs dated No of DD. If I /we fails to commence the work as specified in the above memorandum or is I/we fail to deposit the amount of security deposit

specified against (ii) a in the above memorandum in accordance with the clause I of the said conditions of contract. I/we agree that the said President of India or his successor in office shall/without prejudice to any other right or remedy, shall be retained by him towards such security deposit. I/we further agree that the said President of India or his successor in office shall also be at liberty to cancel the appendice of the tender if I / we fail to deposit security amount as aforesaid.

SIGNATURE AND ADDRESS OF CONTRACTOR

Gra Circle



#### FILE NO-03/ITD/38/2023-2024/W **GOVERNMENT OF INDIA** OFFICE OF SUPERINTENDING ARCHAEOLOGIST ARCHAEOLOGICAL SURVEY OF INDIA AGRA CIRCLE, THE 22 MALL ROAD, AGRA

DATE OF OPENING: 14/03/2024at 15:30 Hrs. TENDER DOWNLOADED TILL 13/03/2024at 15:00 Hrs.

NAME OF WORK: STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA

I/We hereby tender for the President of India of the materials described in the under mentioned memorandum according to the specification within the times specified and at the rates specified therein subject to the conditions to the contractor:

#### **MEMORANDUM**

- (I) EARNEST MONEY RS. 31,966/- (THIRTY ONE THOUSAND NINE HUNDRED SIXTY SIX ONLY)
- (II) SECURITY DEPOSIT Rs. 70,931.00 (Rs. SEVENTY THOUSAND NINE HUNDRED THIRTY ONE) ONLY.
- (III) PAYABLE IMMEDIATELY ON THE ACCEPTANCE OF THE TENDER (SECURITY DEPOSIT) ---
- (IV) PERCENTAGE TO BE DEDUCTED FROM BILL: Income tax and other taxes as applicable by the government
- (V) PLACE OF WORK- CHINI-KA-RAUZA, AGRA.

I. 10	Description of Supply of Materials works		Quantity		Tota amoun t (in words)
1.	Earth work in excavation by manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Rate Including GST).	14.76	Cum		
2.	Tile brick masonry with common burnt clay F.P.S. (non modular) tile bricks of class designation 10 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand) (Rate Including GST).	14.30	Cum		
3.	Taking out lakhauri brick work manually for fixing of Y Shape Post of concertina coil fencing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (Rate Including GST).	2.71	Cum		
4.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) (Rate Including GST).	2.71	Cum		
5.	Supply & Fixing at site Angle iron for Y-shape, post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes up to 10 mm dia. etc. complete with welding & cutting. (Rate Including CST)	603.00	Kg		
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) (Rate Including GST).	3.33	Cum		
7.	Repairing Charges for M.S. Iron Gates Such as iron frames (50x50x6)mm size, 12mm Square Bar, M.S. Flat 50x5 mm, Gusset plate 6mm thick at corners & center, hinges and locking arrangement as per required and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).	1.00	Job		
3.	Providing & fixing of M.S. Jaal on Well of required pattern with angle iron frames (65x65x6) mm size graded with 50x50x6 mm angle c/c 50 cm, having flat 40x6 mm c/c 10 cm and covered with iron mesh Jalie and nut bolts including cutting fabricating welding and applying a priming coat of approved steel primer using structural steel etc. complete (Rate Including GST).	384.83	Kg		
9.	Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge. (Rate Including GST).	47.25	Sqm		
10.	Supply & Fixing Red sand stone benches having 2 legs of size 0.50x0.20x0.45 m with simple moldings and 80 mm thick red sand stone top size 1.50x0.45 m as per design and matching to the existing pattern at site. (Rate Including GST).	10.00	Nos		
11.	Provision for Purchase and installation at site of readymade Dustbins of Red Sand Stone of Cylindrical shape in single block having top molding and depression as per design on extra surface fully open top outer top dia 580mm and height 750mm of required shape & design. (Rate Including GST).	3.00	Nos	- Up	rinten al Su
12.	A Coto including cutting tanticaling	76.81	Kg	10 Color	CAL SI

	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture. (Rate Including GST).	116.80	Sqm
14.	Providing & fixing of G.I. Barbed wire Fencing with existing Red Sand Stone Final placed barbed wire weighting 9.38 kg per100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Rate Including GST).	840.00	Rmt
15.	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All	150.00	Sqm
16.	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 of a bed of 12 mm mud mortar, including filling joints with Jamuna sand, with common burnt bed of 12 mm mud mortar, including GST).	150.00	Sqm
17.	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mind dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks in the paid songgrately) (Rate Including GST).	158.00	Sqm
18.	Providing & fixing M.S. gates of required pattern with angle iron frames (50x50x6)mm size graded with 10 cm c/c Sq. bars 12mm size pointed at the top extra with same curved bar and each frame having Gusset plate, 6mm thick at corners & center and provision for hinges and locking arrangement with M.S. iron gurders of required size and nut bolts including cutting fabricating welding etc. complete. (Rate Including GST).	583.20	Kg
19.	Supply of 1st quality Unslaked lime in sealed air tight bags. (Gotan) (Rate Including	110.69	Qtl.
	CST)	17.60	Cum.
20.	Supply of Surkhi of 1st class well burnt bricks. (Rate Including GST).  Supply of Sieved Coarse Sand (Screened) free from lumps, dust, silt & organic	17.60	Cum.
21.	impurities - Kalpi/Dholpur Quarry. (Rate Including GS1).		
22.	o I - Hakhouri Prioke Nominal Size (Rate Including Gol).	30.52	Cum.
23.	Supply of Brick Ballast of Lakhori Brick/ 1st class srick 25 mm size (Rate Including GST).	25.02	Cum.
24.	Supply of White lime of lst Quality. (Rate Including GST).	33.58	Kg.
25.	a Lat Markle Chine (Pate Including GST)	67.15	Kg.
26.	Supply of Red Sand Stone size 65 mm thick (Bansi Panarpur). (Rate	10.20	Sqm
27.	the state of different cize of ner site requirement industry	3.87	Cum.
	Supply of Brick Jeera of 1st class brick (Rate Including GST).	8.25	Cum.

eine comite e pla inni striga in via liporigi a car avete i avallata care SIGNATURE OF CONTRACTOR



#### (TECHNICAL ELIGBILITY CRITERIA) ELIGIBILITY CERTIFICATES TO BE ENCLOSED BY THE COMPANY/ FIRM/ AGENCY/ CONTRACTOR

- BUPAIT WORK AT CHINERY

The tendering for execution of work Company/Firm/Agency/Contractor should submit the

SI. NO.	ving documents (self-attested copy).  REQUIREMENT	RELEVENT DOCUMENT TO BE PROVIDED	Enclosed Yes/No	PAGE NO. Of Bid Document
1.	The firm/Agency should have registration in ASI / any central Government department or State PWD for civil work.	Copy of Registration certificate to be provided	Yes/No	
2.	The Firm/ Agency/ Contractor should be registered with GST.	Copy of Registration Certificate to be provided	Yes/No	
3.	The Firm/Agency should have Income Tax Return for three financial year 2019-2020, 2020-2021 and 2021-2022 (A.Y. 2020-2021, 2021-2022 & 2022-2023).	Copy of I.T.R for financial year 2019-2020, 2020-2021 and 2021-2022 (A.Y. 2020-2021, 2021-2022 & 2022-2023).	Yes/No	
4.	Pan Card	Copy of Pan Card should be provided	Yes/No	
5.	The firm/agency should have average annual financial turnover for financial year (i.e. 2019-2020, 2020-2021 and 2021-2022), should be at least 30% of the tender cost i.e. Rs. 3,83,586/ A certificate in this regard issued by the CA has to be submitted.	Copy to be provided (Balance Sheet will not be valid)	Yes/No	
6.	The firm / agency should have experience for similar nature of work at least three works each costing not less than 40% of the tender cost i.e. 5,11,448/- OR Two works each Costing not less than 50% of the tender cost i.e. Rs. 6,39,310/- OR One work costing not less than 80% of the tender cost i.e. Rs. 10,22,896/ and those work/works should have been completed in the last seven years ending last day of the month, previous to the month of floating of the	Certificate must contain amount in which work completed)	Yes/No	
7.	EMD (in FDR form) or Exemption Certificate.	Copy to be provided		
8	. I Have an letter board and	Copy to be provided	I. Yes/No	)

1. Similar Nature of Works Means:- The bidder should have the experience of supply of materials for conservation work or the complete work for the conservation of heritage sites/ monuments, least land land

2. Those Bidders who have not mentioned page number against the above point 1-8 in the column of PAGE NO. Of Bid Document will not be evaluated and may be rejected in Technical Stage.

3. The bidders are requested to enclose only required documents.

4. For experience against Para 6 both work order and its completion certificate is mandatory. The copy of work order without completion certificate and Completion Certificate without AUTHORISED STENATOR Copy of Work Order will not consider.

Ta Circle

1- Vendor will be responsible for timely payment to the supplied manpower and statutory authorities and LEGAL:compliance of all statutory provisions relating to minimum wages/specified contract amount etc. In respect of the person deployed by it in the ASI. The agency has to submit the copy of deposit of EPF/ESI with concerned authority every month as an evidence of payment in accounts of person deployed.

THE TAKE THE CONTRACTOR

- 2- The tendering agency shall also be liable for depositing all taxes, levies, cess etc. On amount of service rendered by it to the Archaeological Survey of India to the concerned tax collection authorities from time to time as per extent rules and regulations on the matter.
- 3- The Provision of the information Technology Act (IT Act) as amended from time to time will be applicable to the vendor and the employees assigned by the vendor to Archaeological Survey of India.

#### Force Measure:-

1- Force measure clause will mean and be limited to the following in the execution of the contract/purchase order placed by Archaeological Survey of India, "if at any time, during the continuance of contract, the performance in whole or in part by either party of any obligation under this contract shall be prevented or deployed by reason of any war, hostility, act of public enemy, civil commission, sabotage, fires, floods, explosions, epidemics, quarantine restrictions, strikes, lockouts or act of God (here in after referred to 'events') provided notice of the happening of such events is given by either party. This shall be reason enough to entitle both to terminate this contract and either party will not have any claim for damage against the other in respect of such non-performance or delay in performance. Deliveries under the contract shall be resumed as soon as practicable after such event has come to an end or ceased to exist, and the decision of the Director General, Archaeological Survey of India as to whether the deliveries have been so resumed or not, shall be final or conclusive, provided further that is the performance is whole or part or any obligation under this contract is prevented or delayed by reason or any such event for a period exceeding 30 days, either party may at its option terminate the contract"

#### ARBITRATION:-

1- Archaeological Survey of India and the selected vendor shall make every effort to resolve amicably, by direct negotiation, any disagreement or dispute arising between them under or in connection with the work order. If any dispute arises between parties on aspects not covered by this agreement, or the construction or operation thereof, or the right or liabilities under these except as to any matters the decision of which is specially provide for by the general or the special conditions such dispute shall be referred to the arbitrator as appointed by Director General, Archaeological Survey of India and the award of arbitration, as the case may be, shall be final and binding on both the parties. The arbitrator with the consent of parties may modify the time frame for making and publishing the awards. Such arbitration shall be governed in all respects by the provision of the Indian Arbitration Act 1996 or later and the rules there under and any statutory modification or re-enactment, thereof. The arbitration proceeding shall be held in New Delhi.

#### APPLICABLE LAW:-

1- The Work will be governed by the laws and procedures established by the Government of India, within the frame work of applicable legislation and enactment made from time to time concerning such commercial dealings/processing.

- 1. The successful bidder is responsible for adhering the norms of Pollution Control Board/Forest ADDITIONAL TERMS AND CONDITION:-Department/TTZ during the execution of work. No material shall be stacked in any part of the road/approach of the road and approach pathway. Before stacking the material, the consultation may be done with the site in-charge and identify the space for the stacking of the material.
  - 2. Only such quantity of the material will be kept at the site which require for work on daily basis to avoid inconvenience to the visitors. In case any additional stack of the material is found with the monument
  - 3. After completion of work within 3 days, all the additional material kept on the site will be removed and the working area will be made in presentable condition same as it was before the start of the work.
  - 4- Violation of the above referred terms and conditions in any project will lead debarment/black which and of the firm.

### INSTRUCTIONS FOR ONLINE BID SUBMISSION

The Bidders are required to submit soft copies of their Bids electronically on the CPP Portal, using valid Digital Signature Certificates. The instructions given below are meant to assist the Bidders in registering on the CPP Portal, prepare their bids in accordance with the requirements and submitting their Bids online on the CPP Portal. More information useful for submitting online Bids on the CPP Portal may be obtained at: https://eprocure.gov.in/eprocure/app.

TIPANYON ON WAR

- Bidders are required to enrol on the e-Procurement module of the Central Public Procurement Portal (URL: REGISTRATION https://eprocure.gov.in/eprocure/app) by clicking on the link "Online Bidder Enrolment" on the CPP Portal which is free of charge.
- As part of the enrolment process, the Bidders will be required to choose a unique username and assign a password for their accounts.
- Bidders are advised to register their valid email address and mobile numbers as part of the registration process. These would be used 21 3)
- Upon enrolment, the Bidders will be required to register their valid Digital Signature Certificate (Class II or Class III Certificates with signing key usage) issued by any Certifying Authority recognized by CCA India (e.g. Sify / NCode / EMudhra etc.), with their profile. 4)
- Only one valid DSC should be registered by a Bidder. Please note that the Bidders are responsible to ensure that they do not lend their
- Bidder then logs in to the site through the secured log-in by entering their user ID / password and the password of the DSC / e-Token.

SEARCHING FOR TENDER DOCUMENTS

- There are various search options built in the CPP Portal, to facilitate Bidders to search active tenders by several parameters. These parameters could include Tender ID, Organization Name, Location, Date, Value, etc. There is also an option of advanced search for tenders, wherein the Bidders may combine a number of search parameters such as Organization Name, Form of Contract, Location, Date, Other keywords etc. to search for a tender published on the CPP Portal.
- Once the Bidders have selected the tenders they are interested in, they may download the required documents / tender schedules. These tenders can be moved to the respective 'My Tenders' folder. This would enable the CPP Portal to intimate the Bidders through SMS / e-mail in case there is any corrigendum issued to the tender document.
- The Bidder should make a note of the unique Tender ID assigned to each tender, in case they want to obtain any clarification / help from 3) the Helpdesk

PREPARATION OF BIDS


- Bidder should take into account any corrigendum published on the tender document before submitting their Bids.
- Please go through the tender advertisement and the tender document carefully to understand the documents required to be submitted as part of the Bid. Please note the number of covers in which the bid documents have to be submitted, the number of documents -2) including the names and content of each of the document that need to be submitted. Any deviations from these may lead to rejection of
- Bidder, in advance, should get ready the Bid documents to be submitted as indicated in the tender document / schedule and generally, they can be in PDF / XLS / RAR / DWF/JPG formats. Bid documents may be scanned with 100 dpi with black and white option which
- To avoid the time and effort required in uploading the same set of standard documents which are required to be submitted as a part of every Bid, a provision of uploading such standard documents (e.g. PAN card copy, annual reports, auditor certificates etc.) has been provided to the Bidders. Bidders can use "My Space" or "Other Important Documents" area available to them to upload such documents. These documents may be directly submitted from the "My Space" area while submitting a Bid, and need not be uploaded again and again. This will lead to a reduction in the time required for Bid submission process.

SUBMISSION OF BIDS

- Bidder should log into the site well in advance for bid submission so that they can upload the Bid in time i.e. on or before the Bid submission time. Bidder will be responsible for any delay due to other issues.
- The Bidder has to digitally sign and upload the required bid documents one by one as indicated in the tender document.
- Bidder has to select the payment option as "offline" to pay the tender fee / EMD as applicable and enter details of the instrument.
- Bidder should prepare the EMD as per the instructions specified in the tender document. The original should be posted/couriered/given 3) in person to the concerned official, latest by the last date of Bid submission or as specified in the tender documents. The details of the DD/any other accepted instrument, physically sent, should tally with the details available in the scanned copy and the data entered during Bid submission time. Otherwise the uploaded bid will be rejected.
- Bidders are requested to note that they should necessarily submit their financial Bids in the format provided and no other format is acceptable. If the price Bid has been given as a standard BOQ format with the tender document, then the same is to be downloaded and to be filled by all the Bidders. Bidders are required to download the BOQ file, open it and complete the white coloured (unprotected) cells with their respective financial quotes and other details (such as name of the Bidder). No other cells should be changed. Once the details have been completed, the Bidder should save it and submit it online, without changing the filename. If the BOQ file is found to be modified by the Bidder, the Bid will be rejected.
- The server time (which is displayed on the Bidders' dashboard) will be considered as the standard time for referencing the deadlines for submission of the Bids by the Bidders, opening of Bids etc. The Bidders should follow this time during Bid submission.
- All the documents being submitted by the Bidders would be encrypted using PKI encryption techniques to ensure the secrecy of the data. The data entered cannot be viewed by unauthorized persons until the time of Bid opening. The confidentiality of the Bids is maintained using the secured Socket Layer 128 bit encryption technology. Data storage encryption of sensitive fields is done. Any Bid document that is uploaded to the server is subjected to symmetric encryption using a system generated symmetric key. Further this key is subjected to asymmetric encryption using buyers/Bid opener's public keys. Overall, the uploaded tender documents become readable only after the tender opening by the authorized Bid openers.
- The uploaded tender documents become readable only after the tender opening by the authorized Bid openers.
- Upon the successful and timely submission of Bids (I e after Clicking "Freeze Bid Submission" in the portal), the portal will give a successful Bid submission message & a Bid summary will be displayed with the Bid no. and the date & time of submission of the Bid
- The Bid summary has to be printed and kept as an acknowledgement of the submission of the Bid. This acknowledgement may be used as an entry pass for any Bid opening meetings.

ASSISTANCE TO BIDDERS

- Any queries relating to the tender document and the terms and conditions contained therein should be addressed to the Tender Inviting Authority for a tender or the relevant contact person indicated in the tender.
- Any queries relating to the process of online Bid submission or queries relating to CPP Portal in general may be directed to the 24x7 CPP Portal Helpdesk Mobile Number - +91 8826246593 Tel: The 24 x 7 Help Desk Number 0120-4200462, 0120-4001002. Superintendin cal Sun 000



den i de alumana e la contraliza

A Circle N

## TENDER ACCEPTANCE LETTER (To be given on Company Letter Head)

Date:

To,

SUPERINTENDING ARCHAEOLOGIST, ARCHAEOLOGICAL SURVEY OF INDIA, The 22, Mall Road, Agra Circle, Agra

SUB: ACCEPTANCE OF TERMS & CONDITIONS OF TENDER.

TENDER REFERENCE NO: 03/ITD/38/2023-2024/W (PIN CODE 282006)

NAME OF TENDER / WORK: - STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA-SUPPLY OF MATERIALS

Dear Sir.

- 1. If We have downloaded / obtained the tender document(s) for the above mentioned 'Tender/Work' from the web site(s) namely: for the work of STRUCTURAL REPAIR WORK AT CHINI-KA-RAUZA, AGRA-SUPPLY OF MATERIALS.
- 2. I/ We hereby certify that I / we have read the entire terms and conditions of the tender documents from Page No. -- to --- (including all documents like annexure(s), schedule(s), etc.), which form part of the contract agreement and I / we shall abide hereby by the terms / conditions / clauses contained therein.
- 3. The corrigendum(s) issued from time to time by your department/ organization to have also been taken into consideration, while submitting this acceptance letter.
- 4. I/ We do hereby declare that our Firm has not been blacklisted/ debarred by any Govt. Department/Public sector undertaking.
- 5. I/ We certify that all information furnished by our Firm is true & correct and in the event that the information is found to be incorrect/untrue or found violated, then your department/ organization shall without giving any notice or reason therefore or summarily reject the bid or terminate the contract, without prejudice to any other rights or remedy including the forfeiture of the full said earnest money deposit absolutely.
- 6. If We agree to complete the work after acceptance of the tender.

Yours Faithfully,

(Signature of the Bidder) with Official Seal



### DECLARATION (To be given on Company Letter Head)

NAME OF TENDER / WORK: - STRUCTURAL	REPAIR	WORK	AT	CHINI-KA-
RAUZA, AGRA-SUPPLY OF MATERIALS				

- ----- signatory of the agency/ 1. I,----- Son/Daughter of Shri --Firm mentioned above, is competent to sign this declaration and execute this tender document
- 2. I have carefully read and understood all the terms and conditions of the tender and undertake to abide by them:
- 3. My agency has not been blacklisted/ debarred from participating in tender by any Ministry, Department of Government of India and Government of India undertaking in the last Three (3) Years as on date of opening of this Tender.
- 4. The information/ documents furnished along with the above application are true and authentic to the best of my knowledge and belief.
- 5. I/ We am/ are well aware of the fact that furnishing of any false information/ fabricated document would lead to rejection of my tender at any stage besides liabilities towards prosecution under appropriate law:

ofroc' at his moral a

Signature of authorized person

Date: Place:

Full Name: Seal:

